



Aquatic Facility Design INCORPORATED

Aquatic Facility Designers and Consultants

183 Moore Street · Millersburg, Pennsylvania 17061 · (800) 680-SWIM · Fax (717) 692-3280

Issue Date: February 6, 2025

Addenda 1

Item #1 Per the plans and specifications, all in-pool tile shall be acid cleaned to remove calcification and all loose grout shall be removed and the tile regouted. This work procedure shall remain unchanged.

Change number 1 however shall be that all the ramp wall and floor tile shall be replaced in kind and with non-skid tiles on all walking surfaces. Installation and grouting shall follow existing specifications **Section 09 3213 Swimming Pool Tile**

Item #2 Deep well slide marked as “replace in kind” shall be replaced with **Natural Structures Model 0072**. Contractor to consult with designer on stair layout prior to order. Owner to choose color.